

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-093-00080-00-00

API NUMBER 5-20-1950

LEASE NAME Miller K

WELL NUMBER 1

2540 Ft. from N Section Line

2740 Ft. from E Section Line

SEC. 10 TWP. 23 RGE. 35 (N or W)

COUNTY Kearny

Date Well Completed 6-12-50

Plugging Commenced 5-12-04

Plugging Completed 5-12-04

RECEIVED  
JUN 08 2004

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

KCC WICHITA

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N. Kansas PO Box 2528 Liberal, KS. 67905

PHONE (620) 629-4200 OPERATORS LICENSE NO. 5447

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-11-04 (date)

by Steve Middleton (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? No ACO used in 1950

Producing Formation Chase Depth to Top 2510 Bottom 2648 T.D. 2675

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Surf</u>			<u>480</u>	<u>8 5/8</u>	<u>480</u>	<u>⊖</u>
<u>Prod</u>			<u>2673</u>	<u>5 1/2</u>	<u>2673</u>	<u>⊖</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from feet to feet each section.  
Mixed 500 lb. hulls + 35 sx cmt to plug perfs + anhydrite from 2200 to 1900, pumped mud spacer to 800, then 115 sx from 800 to 0. Anulus was cemented to surface. Cut off 8 5/8 + 5 1/2 + capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.

STATE OF Kansas COUNTY OF Sevier, ss.

(Employee of Operator) or (Operator above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.

(Signature) Verny Lindes

(Address) PO Box 2528 Liberal, KS. 67905

SUBSCRIBED AND SWORN TO before me this 4th day of June, 2004

NOTARY PUBLIC - State of Kansas  
KATHLEEN R. POULTON  
My Appt. Exp. 11-8-06

Kell R. Poulton  
Notary Public

My Commission Expires: November 8, 2006