

6-5 4-070150

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-147-20,445 -00-00

SW NW SW /4 SEC. 24, 02 S, 19 W
1650 feet from S section line
4950 feet from E section line

Operator license# 8628

Lease: Dayton - Credo Well # 12-24

Operator: Credo Petroleum Corporation

County: Phillips 116.97

Address: 1801 Broadway - Suite #900
Denver, CO 80202

Well total depth 3599 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 259 feet
W/170 sxs.

ABAND. oil well , Gas well , Input well , SWD. , D&A

Plugging contractor: Credo Petroleum Corporation License# 8628

Address: 1801 Broadway - Suite #900 - Denver, CO. 80202

Company to plug at: Hour: 9:00 A.M. Day: 5 Month: June Year: 1999

Plugging proposal received from: Don Reitz

Company: Credo Petroleum Corporation Phone: 303-297-2200

Were: 4 1/2" casing set at 3598' w/200 sxs. D.V. Tool at 1461' w/620 sxs cwc.

Perfs: 3310' - 3492'.

Fluid level 2900' from surface.

Ordered out 250 sxs 60/40 pozmix - 10% gel with 500# hulls.

RECEIVED
KANSAS CORP COM
JUN 10 5 20 1999

6-10-99

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All , Part , None

Completed: Hour: 10:30 A.M. Day: 5, Month: June, Year: 1999

Actual plugging report: Allied Cementing pumped 15 sxs 60/40 pozmix - 10% gel pressured up to 800#. Hooked-up to 4 1/2" casing and pumped 180 sxs 60/40 - 10% gel with 500# hulls. Allied ran out of cement. Checked cement level 35' from surface.

Rechecked on 06-07-99 - cement still 35' from surface. Casing volume 155 sxs.

Remarks: Operator sanded back to surface with one sack concrete on top and cut off.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 2201 GL

I did / did not observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED

DATE 6-21-99

INSTR. NO. 61075

100