

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00788-00-00
Spot: CNENESE Sec/Twnshp/Rge: 6-2S-18W
2310 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: IMM B Well Number: 1
County: PHILLIPS Total Vertical Depth: 3497 feet

Operator License No.: 31569
Op Name: BACH OIL PRODUCTION
Address: RR 1, BOX 28
PHILLIPSBURG, KS 67661

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 183 125 SX CMT
Production: Size 5.5 feet: 3469 100 SX CMT \$113.65
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/17/2001 10:00 AM

Plug Co. License No.: 31569 Plug Co. Name: BACH OIL PRODUCTION

Proposal Rcvd. from: JASON BACH Company: BACH OIL PRODUCTION Phone: (785) 543-5615

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel plus 500# hulls.
Top of tubing fish at 1891' - rods and pump out-of-hole.
WLM inside tubing 3475'. T.O.F. at 700'. Hole in casing at 1100'.

Plugging Proposal Received By: DENNIS HAMEL

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 04/17/2001 12:30 PM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Rigged up cementers to 8 5/8" S.P.
Squeezed 50 sxs cement with 50# hulls mixed in cement.
Max P.S.I. 200#. S.I.P. 150#.
Rigged up cementers to 5 1/2" casing.
Squeezed 170 sxs cement with 450# hulls.
Max. P.S.I. 500#. S.I.P. 100#.

INVOICED
DATE 5-7-01
INV. NO. 20010617.67

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 7 2001
05-07-2001
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY. TUBING CAP 7 BBLs - CASING CAP 43 BBLs. TOTAL SLURRY 58 BBLs P

Plugged through:

District: 04

100

Signed

Dennis L. Hamel

(TECHNICIAN)

APR 20 2001

