

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00786-00-~~00~~ 01
Spot: SWSWNE Sec/Twnshp/Rge: 6-2S-18W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: HUFFSTUTTER A Well Number: 6
County: PHILLIPS Total Vertical Depth: 3526 feet

Operator License No.: 31569
Op Name: BACH OIL PRODUCTION
Address: RR 1, BOX 28
PHILLIPSBURG, KS 67661

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 180 125 SX CMT \$114.60
Production: Size 5.5 feet: 3526 150 SX CMT
Liner: Size feet:

Well Type: EOR UIC Docket No: E08461.4 Date/Time to Plug: 04/18/2001 9:00 AM

Plug Co. License No.: 31569 Plug Co. Name: BACH OIL PRODUCTION

Proposal Rcvd. from: JASON BACH Company: BACH OIL PRODUCTION Phone: (785) 476-4254

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Top of tubing fish at 1700'.

Plugging Proposal Received By: DENNIS HAMEL

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 04/18/2001 1:15 PM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Rigged up cementers to 8 5/8" S.P. Squeezed 50 sxs cement with 50# hulls mixed in cement.
Max. P.S.I. 250#. S.I.P. 100#.
Rigged up cementers to 5 1/2" casing. Squeezed down casing as follows:
40/50 sxs cement with 200# hulls mixed in cement. Slight P.S.I.
Continued mixing additional 90/100 sxs cement with 200# hulls mixed in cement - casing on slight vacuum.
Continued mixing 20/25 sxs cement as casing began to pressure up.
Casing and tubing filled to capacity and locked up at 500#. S.I.P. 500#.
(Opened gate and bled off pressure to 200#.)
Note: Tubing capacity - max 9 bbl's
Casing capacity - max 38 bbl's
slurry pumped 53 bbl's down casing.

INVOICED

DATE

5-7-01

INV. NO.

2001061767

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 7 2001

05-07-2001
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY

Plugged through:

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

APR 30 2001

