

15-147-00952-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER N/A  
LEASE NAME Kanzelmeyer  
WELL NUMBER 2  
SPOT LOCATION SE NE SW  
SEC. 6 TWP. 2S RGE. 18 (K) or (W)  
COUNTY Phillips  
Date Well Completed 12/60  
Plugging Commenced 9-17-84  
Plugging Completed 9-17-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Sierra Petroleum Co., Inc.  
ADDRESS P. O. Box 247, Wichita, Kansas 67201

PHONE # (316) 264-8394 OPERATORS LICENSE NO. 5064

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6, Hays, Kansas

Is ACO-1 filed? drillers log if not, is well log attached? yes

Producing formation Lansing Depth to top 3375 bottom 3594 T.D. 3605

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing-K.C.	Limestone	3375	3594	8-5/8"	226'	None
				4-1/2"	3603	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Cemented down 2" tubing with 80 sacks cement (tubing at 1420'). Started circulating at 500 pounds per sq. in. Pulled tubing. Put on 4-1/2" swedge. Mixed 5 sacks cement and pressured up to 400# per sq. in. Hooked up to back side and cemented with 150 sacks cement at 500# per square inch.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. \_\_\_\_\_  
Address P. O. Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Sedgwick, ss. STATE CORPORATION COMMISSION

Jack L. Yinger, Vice President (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack L. Yinger  
(Address) P. O. Box 247, Wichita, Ks. 67201

SUBSCRIBED AND SWORN TO before me this 26th day of September, 1984

ALDINE M. JOHNSON  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appointment Expires:  
3-19-85

Aldine M. Johnson  
Notary Public

Form CP-4 1-84  
Revised 06-83

Phone 913 433-2627, Russell, Kansas  
 Phone 913 93-5861, Great Bend, Kansas

15-147-00952-00-00

Phone Plainville 913-434-2812  
 Phone Kiowa 316-825-4618

**ALLIED CEMENTING CO., INC.**

N<sup>o</sup> 38093

Home Office P. O. Box 31

Russell, Kansas 67665

Date	9-17-84	Sec.	6	Twp.	2	Range	18	Called Out	8:00AM	On Location	12:30 PM	Job Start	1:00 PM	Finish	3:00	
Lease	KANSLEMEYER #2			Location			Phillipsburg 10N 34W NS			County	Phillips	State	Kansas			
Contractor	OSTROM Well Service															
Type Job	OLD HOLE Plug															
Hole Size															T.D.	
Csg. Size	4 1/2"														Depth	
Tbg. Size	2"														Depth	1420'
Drill Pipe															Depth	
Tool															Depth	
Cement Left in Csg.															Shoe Joint	
Press Max.															Minimum	
Meas Line															Displace	
Perf.																

Owner  
 To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.

Charge To **SIERRA Petroleum**  
 Street **PO Box 232**  
 City **Russell** State **Ks 67665**  
 The above was done to satisfaction and supervision of owner agent or contractor.

Purchase Order No. \_\_\_\_\_  
 X *Harmon*  
**CEMENT**

**EQUIPMENT**

Pumptrk #61	No	Cementer	<i>Alan</i>
		Helper	<i>Harmon</i>
Pumptrk	No	Cementer	
		Helper	
Bulktrk #150		Driver	<i>Chris</i>
Bulktrk		Driver	
DEPTH of Job			
Reference	Pump truck chrg 340.00 1.00 PER MILE 51.00 Sub Total <b>391.00</b> Tax Total		

Amount Ordered	235 SK 50% Poz 10% gel 5	
Consisting of		
Common	118 SK @ 5.00	590.00
Poz. Mix	117 SK @ 2.10	245.70
Gel.	24 SK @ 7.25	174.00
Chloride		
Quickset		
Hulls	4 SK @ 14.00	56.00
Sales Tax		
Handling	90¢ PER SK.	236.70
Mileage	66¢ PER Tow mile	332.00
		STATE CORPORATION COMMISSION Total
		(SEP 27 1984)
		Conservation Division Wichita, Kansas
		Total <b>1,634.40</b>
Floating Equipment		

Remarks: Mixed 80 SK cement w/ Hulls down tubing & started circulating. 500 PSI. Came out of hole w/ tubing, put on 4 1/2 sledge mixed 5 SK cement & pressured up to 400 PSI & shut in. Hecker up to back side & mixed 150 SK cement @ 500 PSI max.  
 21 11...

15-147-00952-00-00

SIERRA PETROLEUM CO., INC. ET AL - Operator

WELLSHOOT #2  
SE NE SW  
Sec. 6-25-28  
Phillips County, Kansas

T. D.: 3603'  
Elev.: 2227' KB

Commenced: 12-1-60  
Completed: 12-10-60

CASING:

8-5/8" Set at 226'  
4-1/2" Set at 3603'

CEMENT:

with 195 cc. cement  
with 190 cc. cement

FORMATION

DEPTH

Surface Soil & Clay  
Shale  
Shale & Sand  
Shale  
Sand & Shale  
Shale  
Shale & Sand  
Shale  
Anhydrite  
Shale & Shells  
Lime & Shale  
Lime  
Lime & Shale  
Lime  
Lime & Shale  
Lime

30  
72  
130  
240  
1510  
1645  
1725  
1795  
1825  
2330  
2660  
2790  
2920  
3045  
3132  
3605

TOPS:

Anhydrite  
Beckner  
Ternoto  
Kansas City

1795  
3332  
3399  
3375

STATE OF KANSAS )  
COUNTY OF RUSSELL ) ss:

I hereby certify that the above information is true and correct to the best of my knowledge.

*C. D. Henderson*

Subscribed and sworn to before me this 12th day of December 1960.

*Gray D. [Signature]*  
Notary Public

My commission expires: 10-17-63

RECEIVED  
STATE CORP. & COMMISSION  
SEP 27 1961  
9-27-84  
CONSERVATION DIVISION  
Wichita, Kansas