


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-147-00545-00-00

NORTH



Locate well correctly on above
Section Plat

Phillips County. Sec. 6 Twp. 2 Rge. 18 ~~XX~~ (W)
Location as "NE/CNW%SW%" or footage from lines SE SE SW
Lease Owner Sierra Petroleum Co., Inc. (Formerly Trans Era Pet.)
Lease Name Kanzelmeyer D Well No. 1
Office Address 420 West Douglas, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Was producing oil
Date well completed 6/16/52 19
Application for plugging filed 6/3/55 and 7/2/56 19
Application for plugging approved 6/2/55 19
Plugging commenced 7/4/56 19
Plugging completed 7/25/56 19
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production July 2, 1956 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Lansing/KC Depth to top _____ Bottom _____ Total Depth of Well 3485 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	196	None
				5 1/2"	3484	1150'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING REPORT

Plugged back with crushed rock to 3475', dumped 4 sax cement with dump bailer.
Top of cement, 3450'. Filled hole with mud to 190', set rock bridge, dumped
15 sax cement. Top of cement 140'. Filled with mud to 35', set rock bridge,
dumped 10 sax cement for cap. Job Completed 7/25/56 at 6:30 PM.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Co.
Address Great Bend, Kansas License # 12

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
S. P. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. P. Hall
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of August, 19 56
Leroy Hiets Notary Public.

My commission expires 10-17-59

PLUGGING
FILE SEC 6 T 2 R 18W
BOOK PAGE 76 LINE 32

STATE CO. 08-02-1956
AUG 2 1956
CONSERVATION DIVISION
Wichita, Kansas

A. B. Drilling, Inc.
Kanzelmeier "D" No. 1

SS SW Sec. 6-2-12
Phillips County, Kansas

Total Depth: 3485'
Comm. 6/2/52
Comp. 6/15/52

15-147-00545-00-00

Casing

8 5/8" Set 196'
5 1/2" Set 3485'

Cement

130 sacks Lone Star
150 sacks Lone Star

Formation	Depth
Shale-shells	960
Hard-pyrite	1117
Shale-shells	1250
Hard sand-pyrite	1275
Shale-shells -	1340
Red fat-shale-shells	1370
Shale-lime	1390
Shale	1395
Lime-shale	1410
Sandy lime	1425
Lime-shale	1450
K. G. lime	1470
Lime	3485

STATE OF KANSAS }
NESSLER COUNTY } ss

I hereby certify that the above information is true and correct to the best of my knowledge.

Sara Baf

Subscribed and sworn to before me this 19th day of June, 1952.

Margie Cooper
Notary Public

My commission expires: ~~6-17-54~~
1-30-57

PLUGGING
FILE SEC 6 T 2 R 18W
BOOK PAGE 76 LINE 32