

15-147-20242-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Phillips County. Sec. 11 Twp. 2S Rge. 19W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW NW

Lease Owner John O. Farmer, Inc.

Lease Name Reece Well No. #1

Office Address Box 352 Russell, Kansas 67665

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-21-78 19

Application for plugging filed Yes 19

Application for plugging approved 19


Plugging commenced 19

Plugging completed 2:00 p.m. 8-21-78 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug #1 1050' w/70 sx. cement
Plug #2 215' w/20 sx. cement
Plug #3 40' w/10 sx. cement

STATE OF KANSAS

AUG 24 1978

CONSERVATION DIVISION
WICHITA, KANSAS

8-24-78

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor John O. Farmer, Inc.

Address Box 352 Russell, Kansas 67665


STATE OF Kansas, COUNTY OF Russell, ss.

John O. Farmer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John O. Farmer

Box 352 Russell, Kansas 67665 (Address)

Subscribed and sworn to before me this 23rd day of August, 1978



My commission expires February 15, 1979

Helen Carlson Notary Public

Operator **John O. Farmer, Inc.** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. **#1** Lease Name **Reece** Dry Hole

S11 T 2S R 19W^E

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale & Sand	-0-	1650	Anhydrite	1821' (+449)
Red Bed	1650	1821	Heebner	3384' (-1114)
Anhydrite	1821	1834	Toronto	3411' (-1141)
Shale & Shells	1834	2430	Lansing	3430' (-1160)
Shale & Lime	2430	3360	B/KC	3626' (-1356)
Lime & Shale	3360	3445	TD	3635' (-1365)
Lime	3445	3635		
<p>DST. #1 3440'-to 3470' Tool Open: 30-30-10-30; weak blow Rec: 40' drilling mud IFP: 21-21 FFP: 32-32 BHP: 739-719</p> <p>DST. #2 3465' to 3495' Tool Open: 30-45-60-60; fair blow Rec: 180' muddy water IFP: 43-53 FFP: 75-75 BHP: 983-961</p> <p>DST. #3 3565' to 3581' Tool Open 5 min. Shut in 30 min. blow 2 min. Rec: 5' mud All pressures zero</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>John O. Farmer</i>
	Signature
	President
	Title
	August 23, 1978
	Date