


15-147-00082-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Phillips County, Sec. 8 Twp. 2S Rge. 19W (E) (W)

Location as "NE/CNW<sup>1</sup>/<sub>4</sub>SW<sup>1</sup>/<sub>4</sub>" or footage from lines SW SW NW

Lease Owner The Texas Company

Lease Name Martin Bayens Well No. 1

Office Address 614 Biting Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed September 9 19 51

Application for plugging filed September 9 19 51

Application for plugging approved September 10 19 51

Plugging commenced September 10 19 51

Plugging completed September 10 19 51

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3930' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"	359'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGED AS FOLLOWS:

- 3930-300 - Heavy Mud
- 300 - Dry Hole Plug
- 200-250 - 20 Sacks Cement
- 250-30 - Heavy Mud
- 30 - Dry Hole Plug
- 30-Bottom of Cellar - 10 Sacks Cement

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 18 1951  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to 9-18-51

Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.

M. C. Harrell (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. C. Harrell

614 Biting Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 18th day of September, 19 51

H. Howard Fister Notary Public.

My commission expires September 20, 1952

8 2 19w  
108 31



## LOG OF WELL

SHEET No. 2District Kansas Owner The Texas Company Farm Martin Bayens Well No. 1

FORMATION	AMOUNT	COLOR	HARD OR SOFT	DEPTH CORES TAKEN	REMARKS
Surface Soil & Clay	100				<u>CASING RECORD:</u> 10-3/4" casing set at 357' w/225 sacks cement & 200# CC.  <u>ELEVATIONS:</u> 2249-----KB 2247-----DF 2245-----GL  <u>TOPS:</u> Topeka-----3232 Heebner-----3444 Lansing-----3473 Kansas City--3712 Arbuckle-----3853
Sand	155				
Rock	245				
Shale & Shells	995				
Sand	1210				
Sand & Shale	1620				
Red Bed, Shale & Shells	1870				
Anhydrite	1920				
Red Bed & Shale	2180				
Red Bed, Shale & Shells	2445				
Lime & Shale	2550				
Lime	2615				
Lime & Shale	2975				
Lime	3050				
Shale & Lime	3115				
Lime	3720				
Lime & Shale	3853				
Arbuckle	3930				
Total Depth	3930				

REMARKS:

- 9-6-51 Ran DST #1 from 3523-35, open 35 minutes, recovered 14' drilling mud, no oil, gas or water. BHP 680# in 15 minutes.  
 Ran DST #2 from 3568-90, open 30 minutes, recovered 2400' salt water. BHP 1150# in 15 minutes.
- 9-9-51 Ran DST from 3853-61, open 1 hour, had slight blow for 2 minutes, recovered 10' drilling mud.
- 9-10-51 Plugged and abandoned.