

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
15-147-00800-00-00

~~15-147-19067-00-00~~
API NUMBER Completed 6-8-51
LEASE NAME Kanzelmeyer C
WELL NUMBER 2
4290 Ft. from S Section Line
2310 Ft. from E Section Line
SEC. 7 TWP. 2 SRGE. 18 (E) or (W)

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum Management, Inc
ADDRESS 14201 E. Central Wichita, KS 67230
PHONE# (316) 733-5600 OPERATORS LICENSE NO. 5242

COUNTY Phillips
Date Well Completed 6-8-51
Plugging Commenced 10-24-96
Plugging Completed 10-24-96

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)
The plugging proposal was approved on 10-24-96 (date)
by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? Filed w/ Application
Producing Formation TOPENA - LKC Depth to Top 3082 Bottom 3456 T.D. 3456

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8	190	0
				5-1/2	3454	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Perforate 3 shots @ 1085' + 1775'. Pump 25 Sx 60/40 Poz + 10% Gel + 1 Sx Hulls down 8-5/8.
Pump 75 Sx 60/40 Poz + 10% Gel + 4 Sx Hulls, 10 Sx Gel Spacer, 150 Sx 60/40 Poz + 10% gel
down 5/2

Name of Plugging Contractor Allied Cementing License No. 11-21-96
Address P.O. Box 628, Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ralfe D. Reber
STATE OF KANSAS COUNTY OF Sedgewick, ss.

Gary L. Reed Agent (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.
(Signature) Gary Reed
(Address) As Above

SUBSCRIBED AND SWORN TO before me this 20th day of November, 19 96
Dana R. Clothier
Notary Public

My Commission Expires: 11/13/2000

