

Orig - State Corp. Comm
Copy - B. A. Conner - 357 FPB
Copy - Mary Crump - Okla City
Copy - Well File

Copy - Terra Resources, Inc.

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1982

6-21-82

Give All Information Completely
Make Required Affidavit

WELL PLUGGING RECORD

15-147-00837-00-01

CONSERVATION DIVISION

COUNTY Phillips SEC. 13 TWP. 2 RGE. 19 x E/W
Location as in quarters or footage from lines:

NE SE NE

Locate Well
correctly on above
Section Platt.

Lease Owner Phillips Petroleum Company
 Lease Name Huffstutter Coop Unit Well No. 6W04 (6M04)
 Office Address Box 287, Great Bend, Kansas 67530
 Character of Well (Completed as Oil, Gas or Dry Hole) WI
 Date Well Completed 4-9-82
 Application for plugging filed 4-29-82
 Plugging commenced 6-10-82
 Plugging completed 6-17-82
 Reason for abandonment of well or producing formation No further use to lease

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
 Producing formation Perfs plugged off in 1972
 Depth to top _____ bottom T.D. 2730' PB
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	Water	0'	212'	8 5/8"	212'	-0-
Production	Oil & Water	0'	3316'	5 1/2"	3316'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. On 6-10-82 MIRU Kelso Casing Pullers & ran SIM to 2230'. Mixed & Pmpd 3 sx gel & 6 BW down annulus. Mixed & Pmpd 2 sx gel, flushed w/25 BW. Max press - 200 PSI. Still getting oil & water flowback. Perf one hole by Welex @ 400'. Pmpd 3 BW - flowed back. Pmpd 33 BW - flowed back. Shot csg @ 1200'. No csg recovered. RDMO Kelso Csg Pullers. Hallib pmpd 5 1/2" plug, 50 sx cmt w/6% gel & 3% CaCl. Pmpd 5 sx hulls, 100 sx cmt w/6% gel & 3% CaCl. SI. Conn to 8 5/8" & pmpd 50 sx cmt w/6% gel & 3% CaCl & 5 sx hulls, 100 sx cmt w/6% gel & 3% CaCl. Max press 550 PSI. SI Conn to 5 1/2" - Pmpd 50 sx cmt w/6% gel & 3% CaCl @ 200 PSI. SI. Cut off 8 5/8" & 5 1/2" csg 5' below GL. Welded on plate. Well P&A 6-17-82


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pullers Halliburton
Chase, Kansas Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.

C. D. Dohrer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C D Dohrer Area Mgr.
Box 287, Great Bend, Kansas
 (Address)



SUBSCRIBED AND SWORN TO before me this 18th day of June, 19 82

My Commission expires: February 15, 1984

Velma L. Mog
 Notary Public.

