

15-147-00821-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Phillips SEC. 12 TWP. 2S RGE. 19W E/W
Location as in quarters or footage from lines:
SE/4 SE/4 SE/4

Locate Well
correctly on above
Section Platt.

Lease Owner Phillips Petroleum Co.
Lease Name Huffstutter #2-4 Well No. _____
Office Address Box 287, Great Bend, Ks. 67530
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 3/26/81
Plugging completed 4/1/81
Reason for abandonment of well or producing formation _____
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation _____ Depth to top _____ bottom T.D. 3364'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	1838'	None
				5-1/2"	3357	2352'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Took stretch. Made shot at 2625'. Went up to max pull and pipe parted. Changed out clips. Ran fishing tool in hole. Could not get over 5 1/2 collar - wrong size grapple in overshot. Ran overshot back in hole. Hooked onto casing - not loose. Made shots at 2532, 2470 and 2332. Pulled 8 joints. Broke fishing tool off. Pulled 8 more joints. Pumped 35 sacks cement, 7 sacks gel, 21 bbl water. Pulled 30 joints to 960'. Pumped 50 sacks cement, 5 sacks gel, 5 bbl water; pulled 19 joints. Pumped 50 sacks cement and pulled balance of casing. (Total pulled 74 joints). Pumped 5 sacks cement. Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of April 1981

My Commission expires: _____



Joan Kelso - 71981
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

Rec'd
4-7-81

Formation Record

15-147-0082100-00

Lease Argan

Huffstutter Unit 2-4

Well No. 4

FROM	TO	Formation	REMARKS
0	70	Surface Soil	ELEVATION: 2159' Ground Section 12-28-19W SE SE SE Phillips County
70	670	Shale	
670	970	Sand and Shale	
970	1065	Shale, Lime, and Shells	
1065	1100	Sand	
1100	1115	Lime	
1115	1245	Shale and Shells	
1245	1430	Sand, Lime, and Shells	
1430	1500	Lime	
1500	1640	Shale	
1640	1791	Shale, Lime, and Sand	Top Anhydrite 1695'
1791	1851	Lime	
1851	2010	Lime and Shale	
2010	2093	Shale	
2093	2240	Red Bed and Shale	
2240	2350	Lime, Shale, and Red Bed	
2350	2925	Shale	
2925	3160	Lime	
3160	3190	Shale	
3190	3364	Lime	Top L.K.C. 3265'

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 23 1980
 CONSERVATION DIVISION
 Wichita, Kansas