

4-041811

API Number: 15- - 06-08-51

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

10-24

SW NW NE /4 SEC. 07, 02 S, 18 W
990 feet from N section line
2310 feet from E section line

Operator license# 5242

Lease: Kanzelmeyer Well # C-2

Operator: Petroleum Management, Inc.

County: Phillips 112.32

Address: 14201 East Central
Wichita, Kansas 67230

Well total depth 3456 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 190 feet
w/100sxcmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 24 Month: October Year 1996

Plugging proposal received from: Gary Reed

Company: Petroleum Management, Inc. Phone:

Were: Order 250 sxs 60/40 pozmix with 10% gel with 1/4# F.C. - 500# hulls.
5 1/2" casing set at 3454' w/150 sxs cement. Perf. at 3095' - 3449'. Anhy. at 1775' -
Dakota at 1085'.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All [X], Part [], None []

11-6-96

RECEIVED
NOV 17 - 6 AM '96

Completed: Hour: 2:00 P.M., Day: 24, Month: October, Year: 1996

Actual plugging report: R.U. Cementers to 8 5/8" casing. Squeezed 25 sxs cement with 100# hulls. Max. P.S.I. 300#. R.U. Cementers to 5 1/2" casing. Squeezed 75 sxs cement with 300# hulls followed with 10 sxs gel, followed with 150 sxs cement with 100# hulls. Max. P.S.I. 300#.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING, CASING X. Elevation: GL

I did [X] / did not [] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED
DATE NOV 07 1996
INV. NO. 46933