

4-061131

12-13

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-147-20,582 -00-00

SE SE NE /4 SEC. 02, 02 S, 19 W
2970 feet from S section line
330 feet from E section line

Operator license# 31514

Lease: Siamese Well # 1

Operator: Thoroughbred Associates

County: Phillips 117, 33

Address: 10 Colonial Court
Wichita, Kansas 67207

Well total depth 3610 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 212 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Shields Drilling Company License# 5184

Address: Shields Building - Russell, Kansas 67665

Company to plug at: Hour: 6:30 P.M. Day: 13 Month: December Year: 1997

Plugging proposal received from: Burt Beery

Company: Shields Drilling Company Phone: -

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour 9:30 P.M., Day: 13, Month: December, Year: 1997

Actual plugging report:

1st. Plug at 1800' w/25 sxs. - Anhydrite 1782' - 1802'.

2nd. Plug at 1225' w/100 sxs. - Dakota 916' - 1216'.

3rd. Plug at 265' w/40 sxs. - Surface pipe 212'.

4th. Plug at 40' w/10 sxs.

Rathole with 15 sxs.

Mousehole with 10 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 2216 GL

I did [] / did not [X] observe the plugging.

[Signature]
DH (agent)
Form CP-2/3

RECEIVED
KANSAS CORP COM
DEC 22 2:08 PM '97

INVOICED

DATE JAN 06 1998

INV. NO. 49846

12-22-97