

13-147-00832-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- none

C-SE-SW, Sec. 13, T 2 S, R 19 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Huffstatter Coop Well # 2-W02

Operator: Phillips Pet. Co.
Name & Address Box 287
St. Bend, Mo 67530

County Phillips

Well Total Depth 3357 feet

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 175'

Abandoned Oil Well X Gas Well _____ Input Well FOR ops 6-15-04 SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing License Number _____

Address Hays, Kansas

Company to plug at: Hour: 10:00AM Day: 5 Month: 11 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Mr. Gene Starns

(company name) Phillips Pet (phone) _____

were: 5 1/2" set @ 3357' - Perfs @ 3323-28',

3270-76', 3287-91' (squeezed off), 3292-96', 3341-45,

and open hole 3356-86'. Tubing parted @ 1059'

Hole in ~~log~~ @ 1050' - Unrecovered fish in hole

Ordered 375 sy ⁷⁰/₁₀₀ poz-6 gel & 6 hulls

Signed Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:30PM Day: 5 Month: 11 Year: 1982

ACTUAL PLUGGING REPORT Hooked up to 5 1/2" csg: pumped

in 25 sy cmt - then 150 sy cmt. w/ 3 sy hulls

in cmt: P.S.I to 500# - Hooked up to 8 5/8" S.P.,

pumped in 300 sy w/ 3 hulls - P.S.I to 300#

(Halliburton)

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

INVOICED

DEC 7 1982

DATE 12-14-82

Signed Dennis L. Hamel
(TECHNICIAN)

12-7-82

CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 1829-w

FORM CP-2/3
Rev. 9-82