

4-061127

12-5

-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-147-20,584
SW SW NE /4 SEC. 11, 02 S, 19 W
2970 feet from S section line
2310 feet from E section line

Operator license# 31514
Operator: Thoroughbred Associates
Address: 10 Colonial Court
Wichita, Kansas 67207

Lease: Mousley Well # 1
County: Phillips 117.65
Well total depth 3620 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 208 feet

Aband. oil well, Gas well, Input well, SWD, D & A

Plugging contractor: Shields Drilling Company, Inc. License# 5184

Address: Shields Building - Russell, Kansas 67665

Company to plug at: Hour: 3:00 A.M. Day: 5 Month: December Year: 1997

Plugging proposal received from: Burt Beery

Company: Shields Drilling Company, Inc. Phone: -

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None []

Completed: Hour 5:00 A.M., Day: 5, Month: December, Year: 1997

Actual plugging report:

1st. Plug at 1840' w/25 sxs. - Anhydrite 1816' - 1846'.
2nd. Plug at 1250' w/100 sxs. - Dakota 946' - 1246'.
3rd. Plug at 260' w/40 sxs. - Surface pipe 208'.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

STATE CORPORATION COMMISSION
RECEIVED
DEC 19 1997
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD ___ BAD ___ Anhy.plug: YES ___ NO ___
Bottom plug(in place): YES ___ CALC ___ NO Dakota plug: YES NO ___
Plugged through TUBING ___, CASING ___. Elevation: 2246 GL

I did [] / did not [] observe the plugging.

[Signature]
DH (agent)
Form CP-2/3

12-9-97

INVOICED

DATE DEC 17 1997

INV. NO. 49700