

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21453-00-00
Spot: SESWSW Sec/Twnshp/Rge: 31-9S-19W
330 feet from S Section Line, 4290 feet from E Section Line
Lease Name: PYWELL A Well #: 1
County: ROOKS Total Vertical Depth: 3786 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

PROD Size: 5.5 feet: 3785
SURF Size: 8.625 feet: 208

\$123⁰⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/04/2004 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: KEN VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 200# hulls.
Squeeze holes 1056' - 1660' w/200 sxs.
Drilled to 1035' - casing collapsed - drilled out of hole.
Arbuckle perms only. CIBP at 3765'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/04/2004 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Ran tubing to 1076'.
Allied pumped 65 sxs neat cement cwc.
PTOH. Tied onto 5 1/2" casing.
Allied pumped 85 sxs cement with 200# hulls.
Max. P.S.I. 1000#. S.I.P. 300#.
Hooked up to backside.
Allied pumped 50 sxs cement.
Max. P.S.I. 200#. S.I.P. 100#.

RECEIVED
JUN 09 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

6-9-04
2004061654


Form CP-2/3

JUN 08 2004

31-9S-19W
SE SW SW
330FSL 4290FEL SEC

13010W1

STATE KANS COUNTY ROOKS RE-ISSUE 31-9S-19W
 FIELD MARCOTTE (MULTIPAY) SE SW SW
 OPER PYWELL VENTURE
 WELL A-1 PYWELL
 API 15-163-21453-0000
 SPUD 10/17/1981
 DTD 3786 LTD FTD ARBUCKLE
 WELL CLASS DO 330FSL 4290FEL SEC
 STATUS OIL
 COMP 03/10/1982
 PBTB



LOC Petroleum Information

IP IPP 8 BOPD 1 BW ARBUCKLE - NATURAL
 PROD ZONES: LANSING 3636-3677 GROSS
 ARBUCKLE OPENHOLE 3781-3786
 COMMINGLED

EL: 2229 KB

LOG TOPS:		
STONE CORRAL	1638	+591
TOPEKA	3225	-996
HEEBNER	3434	-1205
TORONTO	3453	-1224
LANSING	3472	-1243
BSE KANSAS CITY	3699	-1470
PENN CONGL	3711	-1482
ARBUCKLE	3780	-1551
TD	3786	-1557

CSGS: 8 5/8 @ 200 CMT
 5 1/2 @ 3781 CMT

DSTS: DST 1 3523-3560 KANSAS CITY REC 45 FT OCM
 INIT OP 30M IFF 60 FFP 71
 FINAL OP 30M IFF 71 FFP 71
 ISIP 476 45M FSIP 418 45M

PERFS: LANSING PERF 3636-3677 GROSS
 ACID 1500 GALS
 NO CORES

OPER ADDRESS: BOX 128, HAYS, KS 67601 CONTR: DREILING DRLG

REISSUE TO: CORRECT DST FORMATION, CONTR, ADD FTG, PERFS, TREATMENT
 REPLACEMENT FOR CARD ISSUED 3/30/82

KS R2-062690