

3 022568

15-001-01824.0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER 20040014-29

SE,SW,NW 1/4 Sec/Twp/Rge S.16-T.26S.-R.18E.

3277 feet from south section line

4289 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well# STEVENS NO. 29

Operator License # 101

County ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 800' feet

Name & FEE FUND PLUGGING

Production Pipe: 1.5" Size Feet 800'

Address

Surface Casing: 8" Size Feet 20'

AB oil well Gas Well SWD Well/ Input Well

E-3435 D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE

Lic. # 30670

Address: 19254 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 1:30P.M. Day: 30 Month: 4 2004

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 1.5" CASING TO APPROXIMATELY 800' THAT HAD

BEEN CEMENTED IN AT T. D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE

AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE AND OUTSIDE THE

1.5" CASING.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part None X

TECHNICIAN

Operations Completed: Hour: 4:00P.M. Day: 30 Month: 4 2004

Actual Plugging Report: 3/4" PIPE WAS RAN INTO THE 1.5" CASING TO 640'. CEMENT

WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 1.5" CASING AT

SURFACE. THE 3/4" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 1.5" ANNULUS TO

575'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 8"

SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED

FROM SURFACE. 182 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (THIS WELL WAS UNNUMBERED ON THE MAP.) (GPS SESSION PT. 29)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 24 2004

CONSERVATION DIVISION
WICHITA, KS

Signed:

Clayton P. Titel
TECHNICIAN

bm