



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

August 19, 1981 8-21-81

RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1981
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Bill Craig of Abercrombie Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: XO Exploration, Inc.

Complete Address: 1726 Lincoln Street, #401, Denver, Colorado

Lease Name: Whitney Well No. 1

Location: SW SW Sec. 21 Twp. 2 Rge. 22 (W)

County: Norton Total Depth: 3695'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Craig was instructed to plug the well as follows:

8 3/8" - 223 - 165 sacks Common 22 gel 30cc Elev. 2238 KB Anhydrite 1819-1850
Circulate hole and fill with mud. Pump 50 sacks cement
through drill pipe at 1490'. Pump 50 sacks cement through
drill pipe at 300'. Fill hole with mud to 40'. Push plug and
1/2 sack hulls to 40' and cap hole with 10 sacks cement.
Cement rat hole with 10 sacks cement.

Very truly yours,

Allen J. Loux
Conservation Division Agent