

State of Kansas



15-137-20006-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
OCT 31 1967
10-31-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bill Hager of Thoroughbred Drlg. Co. has this date requested permission to plug the following described well:

Mr. Hager guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Company,

Complete Address: Petroleum Building, Tulsa, Oklahoma.

Lease Name: Neil W. Reeves Well No. 1

Location: CNE-NW Sec. 5 Twp. 2 Rge. (E)(W) 21

County Norton Total Depth 3759 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hager was instructed to plug the well as follows:

249'--8 5/8" Surface pipe, cement circulated with 140 Sx.
Dakota section from 1050' to 1250'.

Circulate hole with heavy mud. Pull DP to 1300' and displace 100 Sx.
cement thru DP. Pull DP to 250' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent