



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-137-20083-00-00

RECEIVED  
STATE CORPORATION COMMISSION

OCT 11 1972

CONSERVATION DIVISION  
Wichita, Kansas

10-11-72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ross Crawford of Red Tiger Drilling Company has this  
date requested permission to plug the following described well:

Mr. Crawford guarantees payment of the plugging fee.

Operator's full Name: Donald L. Snyder,

Complete Address: 2701 NW 39th, Oklahoma City, Oklahoma.

Lease Name: Green Well No. 1-25

Location: NE-NW-SW Sec. 25 Twp. 2 Rge. (E)(W) 23

County: Norton Total Depth 3698' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Crawford was instructed to plug the well as follows:

210'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 850'.

Circulate hole with heavy mud. Pull DP to 1075' and displace 110 Cu. Ft. cement thru DP. Pull DP to 220' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hullsand 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

H. L. J. J. J.  
Conservation Division Agent