



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 9 1964
 11-9-64
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Herb Mason of Dunne & Gardner Drlg. Co. has this date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Dunne & Gardner Drilling Company, Inc.,

Complete Address: 300 Schweiter Building, Wichita, Kansas.

Lease Name: Schulze Well No. 1

Location: CNW-SW Sec. 18 Twp. 2 Rge. (E) (W) 23

County Norton Total Depth 3750 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mason was instructed to plug the well as follows:

210' -- 8 5/8" Surface pipe, cement circulated with 225 Sx.

Circulate hole with heavy mud, set plug @ 550' and 20 Sx. cement.

"	"	200' with 1/4 sk. hulls &
		20 Sx. cement
"	"	40' with 1/2 sk. hulls &
		10 Sx. cement.

Very truly yours,

 Conservation Division Agent