

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15-137-20165-00-01

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Norton SEC. 32 TWP. 2S RGE. 23W E/W
 Location as in quarters or footage from lines:
75' N of C SE SE

Locate Well
 correctly on above
 Section Platt.

Lease Owner Hummon Corporation
 Lease Name Grunert #2 Well No. _____
 Office Address 400 One Main Place Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 6-17-82
 Plugging completed 6-17-82
 Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
 Producing formation _____ Depth to top _____ bottom T.D. 3602'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	283'	none
				4-1/2"	1733'	none

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

PLUGGED ONLY - NO PIPE RECOVERY

Pumped 3 sacks hulls and 100 sacks 50/50 pos 6% gel 3% ee down 8-5/8" casing and
 140 sacks 50/50 pos, 6% gel 3% ee and 4 sacks hulls down 4-1/2" casing.

Plugging Complete.

RECEIVED
 STATE CORPORATION COMMISSION

JUN 24 1982
 06-24-82
 CONSERVATION DIVISION
 Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 19 82



Irene Hoover
 Notary Public.

My Commission expires:

DRILLERS LOG

No. 2 Grunert

CASING RECORD:

8 5/8" @ 283'
w/180 sx cement

4 1/2" @ 1,733'
w/325 sx cement

TOTAL DEPTH: 3,602'

COMPANY: Hummon Oil Company

CONTRACTOR: Red Tiger Drilling Company

COMMENCED: February 6, 1980

COMPLETED: February 19, 1980

DESCRIPTION:

150' North of C SE/4 SE/4
Sec. 32-T2S-R23W
Norton County, Kansas

ELEVATION: 2,306' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale Rock	0	40	
Rock	40	120	
Shale	120	1876	
Anhydrite	1876	1908	
Shale	1908	2280	
Shale w/Lime Streaks	2280	2505	
Shale & Lime	2505	3022	
Lime	3022	3602	
RTD		3602	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 25th day of February, 1980.

Joyce A. Hagermann
Notary Public

