


15-137-00098-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Norton County. Sec. 27 Twp. 2E Rge. 23 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW

Lease Owner Empire Drilling Company, et al

Lease Name Wallack Well No. 1

Office Address 1121 Union Nat'l. Bk. Bldg., Wichita 2, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed 4-25 1953

Application for plugging filed 4-25 1953

Application for plugging approved 4-25 1953

Plugging commenced 4-25 1953

Plugging completed 4-25 1953

Reason for abandonment of well or producing formation

DRY HOLE

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well ELDON PETTY

Producing formation Depth to top Bottom Total Depth of Well 3660 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	Surface Pipe	0	273	8-5/8	273	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

260' with 15 sacks of cement,
filled with mud to top plug
to 40', 1/2 sack hulls and
10 sacks of cement.

5-5-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Golden Cat Drilling Company

Address Wakeeney, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

I, Dan J. Kornfeld, (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Dan J. Kornfeld

1121 Union Nat'l. Bk. Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4 day of May, 1953

My commission expires May 5, 1956

Mary Weinmeier
Notary Public.



15-137-00098-00-00

LOG

COMPANY: Empire Drilling Company, et al
 CONTRACTOR: Golden Cat Drilling Company
 FARM: Wallack #1
 LOCATION: NW NW NW, Sec. 27-2-23W
 Norton County, Kansas
 COMMENCED: 4-13-53
 COMPLETED: 4-25-53

0	to	70	Clay
70	to	273	Sand and shale
273	to	470	Shale
470	to	650	Shale and shells
650	to	658	Sand
658	to	870	Sandy lime
870	to	1000	Sand
1000	to	1375	Sand and redbed
1375	to	1710	Shale
1710	to	1919	Redbed and shale
1919	to	1949	Anhydrite
1949	to	2190	Shale and shells
2190	to	2425	Shale
2425	to	2615	Lime and shale
2615	to	3080	Shale and lime
3080	to	3235	Lime and shale
3235	to	3338	Lime
3338	to	3480	Lime and shale
3480	to	3514	Shale and lime
3514	to	3615	Lime
3615	to	3627	Lime and shale
3627	to	3630	Lime
3630	to	3645	Broken lime
3645	to	3660	Granite Wash
3660			R.T.D.

ELEVATION: 2354 Kelly Bushings

TOPS: TOPEKA 3226'; HEEBNER 3353; TORONTO 3379'; L-K.C. 3393';
 BASE OF K.C. 3588'; ARBUCKLE 3627'; REGAN SAND 3639'; GRANITE
 WASH 3641'; R.T.D. 3660'.

D.S.T.-- 3360'- 89'
 3546'- 60'
 3608'- 27'
 3625'- 30'

RECEIVED
 5-5-53

C E R T I F I C A T I O N

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log of the Wallack #1, Section 27, Township 2 South, Range 23 West, Norton County, Kansas, as reflected by files of the Empire Drilling Company.

Dan J. Kornfeld
 Dan J. Kornfeld

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 4th day of May, 1953.

Mary Hammer
 NOTARY PUBLIC

MY COMMISSION EXPIRES May 5, 1956

PLUGGING
 FILE SEC 27 T 2 R 23W
 BOOK PAGE 22 LINE 12