

15-137-20155-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Norton SEC. 32 TWP. 2S RGE. 23 W E/W  
Location as in quarters or footage from lines:  
C NE SE


Lease Owner Hummon Corporation  
Lease Name Grunert #1 Well No. \_\_\_\_\_  
Office Address 400 One Main Place Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 6-11-82  
Plugging completed 6-17-82  
Reason for abandonment of well or producing formation  
Depleted

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3623'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	259'	none
				4-1/2"	3622'	1023'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Ran 50' of sand, 4 sacks of cement and pushed bottom plug to 3400'. Shot casing  
@2017', 1810', 1517', 1227' and 1027'. Pulled a total of 25 joints of 4-1/2"  
casing. Plugged well with 3 sacks hulls, 13 sacks gel, 2 sacks hulls, 70 sacks  
50/50 pos, 6% gel, 3% cc, 12 sacks gel, released plug and displaced with 70 sacks  
50/50 pos, 6% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

RECEIVED  
STATE CORPORATION COMMISSION

(Signature) R. Darrell Kelso  
Box 347 Chase, Ks. 67524  
(Address)

JUN 24 1982

SUBSCRIBED AND SWORN to before me this 23rd. day of June, 1982  
Wichita, Kansas



Irene Hoover  
Notary Public.

My Commission expires: \_\_\_\_\_

15-137-20155-00-00

Hummon Corporation  
400 One Main Place  
Wichita, Kansas 67202

- Grunert #1  
- C NE SE Sec. 32-2S-23W  
Norton County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.  
221 S. Broadway, Suite 400  
Wichita, Kansas 67202

Commenced: October 18, 1979  
Completed: October 25, 1979

Drillers Log

Shale	1550
Sand	1665
Anhydrite	1948
Shale	2075
Shale & Shells	2280
Shale & Lime	3400
Lime	3460
Lime & Shale	3560
Lime	3623 RTD

RECEIVED  
STATE CORPORATION COMMISSION  
APR - 5 1982  
CONSERVATION DIVISION  
Wichita Kansas  
4-5-82