

15-137-00281-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Norton County, Sec. 18 Twp. 2S Rge. 23 (E) (W)

Location as "NE/CNWxSWx" or footage from lines C NW SW  
Lease Owner Dunne-Gardner Drilling Co., Inc.  
Lease Name Schulze Well No. 1  
Office Address \_\_\_\_\_  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed November 4, 1964  
Application for plugging filed November 6, 1964  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced November 4, 1964  
Plugging completed November 5, 1964  
Reason for abandonment of well or producing formation dry hole

NORTH



Locate well correctly on above  
Section Flat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3750 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe		-0-	210	8-5/8"	10-30-64	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud to 550', set plug with 20 sacks cement. Mud to 200', set plug with 1/4 sack hulls and 20 sacks cement. Mud to 40', set plug with 1/2 sack hulls and 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 9 1964

11-9-64

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_  
Address \_\_\_\_\_

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Don Gardner (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) \_\_\_\_\_  
300 Schweiter Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of November, 1964

My commission expires November 9, 1965

Marilyn E. Fox  
Marilyn E. Fox Notary Public.

DRILLER'S LOG

OPERATOR: Dunne-Gardner Drilling Co., Inc.  
 300 Schweiter Building, Wichita, Kansas

CONTRACTOR: Dunne-Gardner Drilling Co., Inc.

LEASE: Schulze

WELL: No. 1

LOCATION: C NW SW Section 18-2S-23W  
 Norton County, Kansas

DATE COMMENCED: October 29, 1964

DATE COMPLETED: November 4, 1964

CASING: Set 8-5/8" surface pipe at 210' with 225 sacks  
 cement.

<u>FROM</u>	<u>TO</u>	
0	40	Shale
40	210	Shale and Shells
210	620	Blue Clay
620	1015	Shale and Shells
1015	1075	Sand
1075	1335	Shale and Shells
1335	1460	Sand and Shale
1460	1475	Shale
1475	1620	Green Shale
1620	1770	Sand
1770	2015	Red Bed and Shale
2015	2025	Stone Corral
2025	2245	Anhydrite Lime
2245	3457	Shale and Lime
3457	3680	Lime
3680	3718	Lime and Shale
3718	3750	Lime
3750		Total Depth

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 DEC 15 1964  
 12-15-64  
 CONSERVATION DIVISION  
 Wichita, Kansas


I certify the above to be true and correct to the best of my knowledge and belief.

DUNNE-GARDNER DRILLING CO., INC.

By:   
 Don Gardner

Subscribed and sworn to before me this 9th day of November, 1964.

My Commission Expires:  
November 9, 1965

  
 Marilyn E. Fox, Notary Public