

15-137-20217-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Norton SEC. 21 TWP. 2S RGE. 22WE/W  
Location as in quarters or footage from lines:  
C SW SW


Lease Owner 21-2S-22W  
 Lease Name WHITNEY Well No. 1  
 Office Address 1050 Lincoln Tower Bldg., 1860 Lincoln St.,  
Denver, CO 80295  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed August 20, 1981  
 Application for plugging filed August 20, 1981  
 Plugging commenced August 20, 1981  
 Plugging completed August 20, 1981  
 Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered.  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? YES

Locate Well  
correctly on above  
Section Platt.

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3696'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set 1st plug @ 1490' with 50 sx.  
Set 2nd plug @ 310' with 50 sx.  
Set 3rd plug @ 40' with 10 sx.  
Plug was down 8/20/81,

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 26 1981  
 CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Abercrombie Drilling, Inc. 8-26-81

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Vice Pres. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801. Union Center, Wichita, KS 67202  
 (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of August, 19 81

My Commission expires: 7-13-85

Elizabeth G. Terry  
 Elizabeth G. Terry Notary Public  
 NOTARY PUBLIC  
 STATE OF KANSAS

CONTRACTORS WELL LOG

OPERATOR:	X O Exploration
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	WHITNEY #1
LOCATION:	C SW SW, Sec. 21-2S-22W Norton County, Kansas
SPUD DATE:	August 13, 1981
COMPLETION DATE:	August 20, 1981

0	1770	Sand & Shale
1770	1819	Shale
1819	1850	Anhydrite
1850	2533	Shale
2533	2710	Shale & Lime
2710	3100	Shale
3100	3695	Lime
	3695	Rotary Total Depth

Spud hole @ 7:00 p.m., 8/13/81. Cut 225' of a 12 1/4" hole. Ran 7 jts. of new 24# casing (tally \$216.42) set @ 223.42' with 165 sx. common 3% c.c., 2% gel. Cement did circulate. Plug was down @ 1:00 a.m., 8/14/81. Will drill plug @ 9:00 a.m., 8/14/81.

3696' TD. Set 1st plug @ 1490' with 50 sx. Set 2nd plug @ 310' with 50 sx. Set 3rd plug @ 40' Solid Bridge with 10 sx. 10 sx. in Rathole. Plug was down 8/20/81.

SAMPLE TOPS:

Anhydrite 1819'  
B/Anhydrite 1850'

STATE OF KANSAS )  
 ) SS  
COUNTY OF SEDGWICK )

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 26 1981  
CONSERVATION DIVISION  
Wichita, Kansas  
8-26-81

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the WHITNEY #1, C SW SW, Sec. 21-2S-22W, Norton County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge  
Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 24th day of August, 1981.

Elizabeth G. Terry  
Elizabeth G. Terry  
NOTARY PUBLIC

my commission expires 7-13-85

