


15-137-00241-00-00

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

NORTON County. Sec. 18 Twp. 2 Rge. (E) 22(W)
Location as "NE/CNW%SW%" or footage from lines NE NE NE
Lease Owner EMPIRE DRILLING COMPANY
Lease Name SCHILLING Well No. 1
Office Address 650 FOURTH NATIONAL BANK BUILDING WICHITA, KS.
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed DECEMBER 9, 1957 19
Application for plugging filed DECEMBER 9, 1957 19
Application for plugging approved DECEMBER 9, 1957 19
Plugging commenced DECEMBER 9, 1957 19
Plugging completed DECEMBER 9, 1957 19
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY
Producing formation Depth to top Bottom Total Depth of Well 3740 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	SURFACE	0	177	8 5/8"	177	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

BOTTOM PLUG @ 600', 20 SACKS CEMENT: MIDDLE PLUG @ 170', 15 SACKS CEMENT: TOP PLUG @ 40', 10 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
DEC 17 1957
CONSERVATION DIVISION
Wichita, Kansas

12-17-57

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY
Address 650 FOURTH NATIONAL BANK BUILDING WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
I, DAN J. KORNFELD, CONTRACTOR (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
650 FOURTH NATIONAL BANK BUILDING
(Address)

SUBSCRIBED AND SWORN TO before me this 13TH day of DECEMBER, 19 57

My commission expires JULY 2, 1958
HAZEL PIERSON Notary Public.

PLUGGING
FILE SEC 18 T 2 R 22W
BOOK PAGE 69 LI E 16

15-137-00241-00-00

LOG

COMPANY: EMPIRE DRILLING COMPANY, WICHITA, KANSAS
CONTRACTOR: EMPIRE DRILLING COMPANY, WICHITA, KANSAS
FARM: SCHILLING
LOCATION: NE NE NE SECTION 18-2-22, NORTON COUNTY, KANSAS
COMMENCED: DECEMBER 2, 1957 ELEVATION: 2332 KB
COMPLETED: DECEMBER 9, 1957

0	TO	1913	SHALE AND SHELLS
1913	TO	1941	ANHYDRITE
1941	TO	2245	SHALE AND SHELLS
2245	TO	2490	SHALE AND LIME
2490	TO	2620	SHALE AND SHELLS
2620	TO	2715	SHALE AND LIME
2715	TO	3065	LIME AND SHALE
3065	TO	3190	SHALE AND SHELLS
3190	TO	3300	SHALE AND LIME
3300	TO	3490	LIME AND SHALE
3490	TO	3670	LIME
3670	TO	3740	SHALE, LIME AND GRANITE
		3740	RTD

SET: 8 5/8" 177' WITH 115 SACKS CEMENT

TOPS:	HEEBNER	3386
	TORONTO	3419
	LANSING KANSAS CITY	3431
	BASE KANSAS CITY	3620
	ARBUCKLE	3677
	GRANITE WASH	3691
	GRANITE	3727

CERTIFICATION

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE SCHILLING NUMBER 1, NE NE NE SEC 18-2-22, NORTON COUNTY, KANSAS AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

[Signature]
DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 13TH DAY OF DECEMBER, 1957.

[Signature]
HAZEL PIERSON, NOTARY PUBLIC

MY COMMISSION EXPIRES JULY 2, 1958

RECEIVED
STATE CORP. DIV.
12-17-57
DEC 17 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
18 T 2 R 22W
PAGE 69 LINE 16