

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
300 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-025-20858-00-00  
API NUMBER ~~15-025-20635~~

RECEIVED  
MAY 19 2004  
KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE NAME Minneola  
WELL NUMBER 8-1  
989 Ft. from S Section Line  
1651 Ft. from E Section Line  
SEC. 4 TWP. 30S RGE. 25W (E) or (W)  
COUNTY Clark  
Date Well Completed \_\_\_\_\_  
Plugging Commenced 5-11-04  
Plugging Completed 5-12-04

LEASE OPERATOR Murfin Drilling Co., Inc.  
ADDRESS 250 N. Water Suite 300 Wichita, Kansas 67202

PHONE# (316) 267-3241 OPERATORS LICENSE NO. 30606

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Steve Durant (KCC District Agent's Name).

ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 5450'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	1122'	None
				5-1/2"	5449'	3170'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set.  
Plugged off bottom with sand to 5260' and 5 sacks cement. Cut pipe loose @ 3170', pulled up to 1450', pumped 10 sacks gel, 50 sacks cement and 100% hulls, pulled up to 500', pumped 40 sacks cement and 100% hulls, topped off with 30 sacks cement, 60/40 pos, 6% gel.  
Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 17th day of May, 20 04

[Signature]  
Notary Public

My Commission Expires:

