

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Southern Star Central Gas Pipeline  
Address: 3800 Frederica Street Owensboro, Kentucky  
Phone: (270) 852-5000 Operator License #: 33097  
Type of Well: Gas Storage Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: September 17, 2003 (Date)  
by: Jack Robison (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Bush City Ss. Depth to Top: 598' Bottom: 634' T.D. 634'  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-091-19126 0000  
Lease Name: Craig # O-16  
Well Number: Craig # O-16  
Spot Location (QQQQ): NE-SE-NW  
3630' Feet from  North /  South Section Line  
2970' Feet from  East /  West Section Line  
Sec. 23 Twp. 12 S. R. 23  East  West  
County: Johnson  
Date Well Completed: 5/27/1925  
Plugging Commenced: 3/19/2004  
Plugging Completed: 3/19/2004

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Bush City Ss.	Gas	3'	588'	6.62"	cemented	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

All tubulars pulled from well-bore. Plugged solid with Class A cement, from surface to total depth.

Ran 2" to 590'. Pumped through 2" and filled to surface. Tied onto 6.62" and pumped through perfs. SIP 0#  
Perforated @ 97',, 3 shts./ft.

Total Cement: 234 sks. Class A cement. cut and cap.

Name of Plugging Contractor: Splane Pulling & Roustabout Service License #: 6372

Address: P.O. Box 386 Chanute, Kansas 66270

Name of Party Responsible for Plugging Fees: Southern Star Central Gas Pipeline

State of Kentucky County, Daviess, ss.

Charles C. McConnell / D. Mark Rouse

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature] D. Mark Rouse  
(Address) 3800 Frederica Street Owensboro, Kentucky 42304

SUBSCRIBED and SWORN TO before me this 21<sup>st</sup> day of May, 20 04

[Signature] My Commission Expires: 8-26-07  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 24 2004  
CONSERVATION DIVISION  
WICHITA, KS

[Signature]