

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
05-14-04
MAY 14 2004
KCC WICHITA

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
Blanks must be Filled

15-015-19502-00-00
~~15-015-08,075-00~~

Lease Operator: VESS OIL CORPORATION
Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226
Phone: (316) 682-1537 Operator License #: 5030
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 5/10/04 - 3:00 p.m. (Date)
by: Doug Louis (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Arbuckle Depth to Top: 2359 Bottom: 2366 T.D. 2370'
Depth to Top: N/A Bottom: _____ T.D. N/A
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-015-08,075-00
Lease Name: Hamilton A
Well Number: 18
Spot Location (QQQQ): NE-SE-SE-
1120' Feet from North / South Section Line
200' Feet from East / West Section Line
Sec. 11 Twp. 26S S. R. 04E East West
County: Butler
Date Well Completed: 7/7/19
Plugging Commenced: 5/11/04
Plugging Completed: 5/12/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	sw, sli oil	2359	2366	8-1/4"	2043'	none
				6-1/4"	2359'	none
				10	400	could not find it

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Metal junk in hole to 2302'. Tbg at 2300'. spot 35 sx Class A, 3% cc. Pull tubing. Wireline tag @ 2192'. Orange peel 8-1/4 to -6-1/4. 5-1/2 collar welded on 6-1/4. 2" nipple on 8-1/4. Perf holes at 250'. Circ water down 6-1/4 around outside 8-1/4. Tie on 6-1/4/8-1/4" annulus - holds 500#. Tie onto 6-1/4" mix and pump 225 sx 60/40 pozmix, 4% gel. Slight circ. quit & 6-1/4" on vac. Wireline tag 2 hrs later @ 577. Pump 6-1/4, circ. water outside 8-1/4. Mix and pump 225 sx 60/40 pozmix, 4% gel, 3% cc.. Circ., got cmt at 150 sx out. Collar holding fluid-SI on 100#.


Name of Plugging Contractor: United Cementing and Acid Company, Inc. License #: 30437
Address: 2560 W. 6th, El Dorado, KS 67042

Name of Party Responsible for Plugging Fees: Vess Oil Corporation
State of Kansas County, Sedgwick, ss.

W. R. Horigan (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) W R Horigan
(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 12th day of May
Michelle D. Henning My Commission Expires:
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

hm



United Cementing and Acid Co., Inc.

Oil Well Cementing & Acidizing
 (316) 321-4680 • 800-794-0187 • FAX (316) 321-4720
 2510 West 6th Street • El Dorado, KS 67042

RECEIVED
 MAY 14 2004
 SERVICE TICKET
 5369

CC WICHITA
 DATE 5-11-04
 COUNTY Butler CITY _____

CHARGE TO NESS OIL CORP
 ADDRESS _____ CITY _____ ST _____ ZIP _____
 LEASE & WELL NO. HAMILTON A 18 CONTRACTOR SIMMONS WELL
 KIND OF JOB Old Hole Plug SEC. _____ TWP. _____ RNG. _____
 DIR. TO LOC. Kech Rd & Shonway Rd. 1/4 N - W/S 8:00A OLD NEW

Quantity	MATERIAL USED	Serv. Charge	
450 SX	60/40 P02		500.00
255 SX	CLASS A		
18 SX	GEL		
8 SX	CALCIUM		
511 SX	BULK CHARGE		
MIN	BULK TRK. MILES		
NIC	PUMP TRK. MILES		
	PLUGS		
		SALES TAX	
		TOTAL	

T.D. _____ CSG. SET AT _____ VOLUME _____
 SIZE HOLE _____ TBG SET AT 2300' VOLUME _____
 MAX. PRESS. _____ SIZE PIPE 6 5/8 Cog - 2 7/8 Tub
 PLUG DEPTH 2300 PKER DEPTH _____
 PLUG USED _____ TIME FINISHED 3:00P

REMARKS: 8:00A - Spnt 355x CLASS A 376cc @ 2300' - 9:30 Run line TAG CEMENT @ 2192 -
10:00 WAIT ON WELDER - 11:15 LOAD CSG TO R.H. @ 300' - Rig up on CSE MIX 4 Pump
225 SX 60/40 4662 - 12:00 Shot Down CSG ON UAC - Some CLR OUT 8" - (Pie up BETWEEN
8" 1/2" Held 500 lbs) - WOC - 2:00P Run line TAG CEMENT @ 588' - LOAD CSG CLR Behind
8" - Mix Pump 225 SX 60/40 4662 + 376 cc - CLR CEMENT TO S.I.F - Shot IN w/ 100 lbs
CELLER REMAINED FULL.

EQUIPMENT USED

NAME Mitch Rupp UNIT NO. P-15
Neal Rupp 04
 CEMENTER OR TREATER

NAME _____ UNIT NO. B-7

OWNER'S REP.