



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Paul Dean of Phillips Petroleum Co has this date requested permission to plug the following described well:

Operator's Full Name: Phillips Petroleum Company

Complete Address: Box 287 Wheat Bend, K 67530

Lease Name: Huffnuttler Co Op Unit Well No. 6-M04

Location: NE-SE-NE Sec. 13 Twp. 2 Rge. 19 (E)  (W)

County: Phillips Total Depth: \_\_\_\_\_

Abandoned Oil Well'  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Dean was instructed to plug the well as follows:

8 5/8" @ 212' vic. cmt - 5 1/2" @ 3316 Open hole 3316 -  
47- Peps @ 3249 to 3309 Fill-up to 2753' - set  
3 sk cmt plug @ 2753 - Top of cement to 2730' - Shot  
Casing @ 1200' - pump 5 1/2" plug + 50 sk cmt w/ 6 %  
gel + 3 % cc -> 5 hulls + 100 sk cmt: conn to 8 5/8" ->  
pump 50 sk cmt + 5 hulls + 100 sk cmt mat PSI 550 #  
Conn to 5 1/2" pump add 50 sk cmt - 2004  
PSI.

Very truly yours,

Dennis L. Hamel  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION

JUL 20 1982

7-20-82  
CONSERVATION DIVISION  
Wichita, Kansas