

DISTRICT CONSERVATION AGENT'S REPORT

15-147-00836-00-00

178

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 142-42

LOCATION NE NE NE

SEC. 13 TWP. 2 RGE. 19

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 3 Lease Dusin E 10<sup>th</sup> St.

Operator Co-op Refg & T. Allen Address Co-op Refg Great Bend, Kans

Field \_\_\_\_\_ County Phillips

Total Depth 3347 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 212' circulated with cement - 5 1/2" at 3316' with  
100 sax cement behind. Perforations at 3253'.

Filled with chat to 3240', set 4 sax cement with dump bailer,  
pulled 1008' 5 1/2", filled hole with mud to 212', set rock and  
15 sax cement, mud to 35', set rock and 10 sax cement to  
bottom cellar.

FEB 22 1952

2-22-52

*Eddon J. [Signature]*

District Conservation Agent

Date 2-16-52

PLUGGING  
FILE SEC 13 T 2 R 19  
BOOK PAGE 142 LINE 42