

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 6 1962

6-6-62
CONSERVATION DIVISION
Wichita, Kansas

15-147-00141-00-00

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Phillips

Location: CNE SW Sec. 1 Twp. 2 Rge. _____ (E) _____ (W) 19

Name of Field: _____ Total Depth: 3680

I have this date completed supervision of plugging of:

Lease Name: Van Dyke Well No. 1

Operator's Full Name: Don H. Peaker

Complete Address: Box 1595 Pueblo, Colorado

Plugging Contractor: Barnes & Sons

Address: Russell, Kansas License No. 9

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 12 Noon Day 26 Month 5 Year 62

The above well was plugged as follows:

8 5/8" 213' circulated with cement - 4 1/2" 3680' with 100 sax cement, PB to 3648' - Perf 3477'.

Filled with sand to 3477', set 4 sax cement with dump bailer, pulled 1600' 4 1/2" to 550', circulated hole with heavy mud through 4 1/2" at 550', (19 sax Gel), displaced 20 sax cement through 4 1/2" at 550', heavy mud to 180', displaced 20 sax cement through 4 1/2" at 180', heavy mud to 35', cement 35' to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE 6/4/62

INV. NO. 5118-W