

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-147 00837-00-01

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Phillips Pet. Co. - (Paul Dean)

Complete Address Box 287 - St. Bend, KS 67530

Lease Name Huffstutter Coop Unit Well No. 6-M04

Location NE-SE-NE Sec. 13 Twp. 2 Rge. 19 (East) (West)

County Phillips Total Depth _____

Abandoned Oil Well Gas Well _____ Input Well XEOR086-14-04 SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing

Address Hays, Ks. License No. _____

Operation Completed: Hour: 5:30 PM Day: 14 Month: 6 Year: 19 82

Plugging Operations attended by Agent?: All Part _____ None _____

The above well was plugged as follows:

8 1/2" @ 212' circ emt - 5 1/2" @ 3316
Open hole 3316-47 - Perfs @ 3249 to 3309
Fill-up to 2753' - set 3 sx emt plug @ 2753 - top of
cement to 2730' - Slot casing @ 1200' - Halliburton
pumped 5 1/2" plug -> 50 sx emt w/62 gel + 3% CC -> 5 hulls +
100 sx emt: conn to 8 1/2" -> pmpl 50 sx emt + 5 hulls + 100 sx emt.
Max-PSI - 550# - Conn to 5 1/2" pmpl add 50 sx emt - 200# PSI.

Amount of Surface Casing: 212'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1982
7-20-82
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

7-20-82
674-W