

45-147-00821-00-00

KANSAS

FORM CP-3  
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- -

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name PHILLIPS PETROLEUM COMPANY 67230

Complete Address BOX 287 GREAT BEND, KANS.

Lease Name HUFFSTUTTER Well No. UNIT - 2-4

Location SE-SE-SE Sec. 12 Twp. 2 Rge. 19 (East) (West)

County PHILLIPS Total Depth 3364 FT.

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor NELSO DRILLING COMPANY (MILWARD NELSO)

Address BOX 176 CHASE, KANS. License No. \_\_\_\_\_

Operation Completed: Hour: 4:10 PM Day: 1 Month: APRIL Year: 19 81

The above well was plugged as follows:

8 5/8" 1830 FT SP. CUM 1/1000 ST -> 5 1/2" SET @ 3357 FT 1/150 OMT.  
NO PLUG. BACK. - PERFS 3264' TO 3600' - OPEN HOLE 3357' - 3364'  
PUMPED BOTTOM WITH PUMP TRUCK. PUT 50 ST COMMON OMT @ BOTTOM.  
SHOT PIPE @ - 2600' - 2500' - 2400' + 2342 FT RECOVERED 2342 FT  
ORDERED 140 ST 50/150 FORMIN 6% GEL. + 12 ST GEL.  
PUMPED IN 5 1/2" WITH PUMP TRUCK. -> SPOTTED OMT COMMING OUT OF HOLE.  
SPOTTED - 35 ST OMT. + 7 ST GEL @ 1838 FT + DISPLACED.  
" 50 ST OMT + 5 ST GEL @ 960 FT + DISPLACED.  
" 50 ST OMT @ 270 FT - FILLED HOLE 1/2 OMT. TO SURFACE.

CEMENTED BY SUN RECEIVED  
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

APR - 3 1981

Signed: [Signature]  
Conservation Division Agent, Kansas

INVOICED

DATE 4-6-81

INV. NO. 5036-4