

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

13-147-00835-00-01

AUG 23 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
8-23-71

Operator's Full Name Thos. H. Allam

Complete Address 925 Union Center Wichita, Kansas 67202

Lease Name Culbertson Well No. 1

Location NW NE SE Sec. 13 Twp. 2 Rge. (E) (W) 19

County Phillips Total Depth 3392'

Abandoned Oil Well        Gas Well        Input Well XX SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 3 P Day 19 Month 8 Year 1971

The above well was plugged as follows:

Total Depth 3392' 8 5/8 csg set at 174' cwc 125 sk.

5 1/2 csg set at 3382' cw 75 sk cmt.

5 1/2 csg perf. (3204-3340)

5 1/2 Csg. perf. at 1690' and squeezed with 160 sk gel W/80 bbl crude oil & 60 sk cmt.

No pipe recovered.

Pumped down 5 1/2 csg with 30 sk gel & 30 sk gel & water W/5 sk hulls, released plug and pumped 70 sk cmt. 500 lbs pres.

Pumped down annulus (5 1/2 -8 5/8) with 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. W. T. Massey  
Well Plugging Supervisor

DATE 8-30-71  
INV. NO. 4215-W