

DISTRICT CONSERVATION AGENT'S REPORT

8

TO:

15-147-00545-0000

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 76-32
LOCATION SE SE SW
SEC. 6 TWP. 2 RGE. 18W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Kanzelmeyer "D"

Operator Sierra Petroleum Co. Inc. Address 420 W. Douglas, Wichita, Kansas

Field _____ County Phillips

Total Depth 3485 Feet.

Plugging Contractor Miller Casing Pulling Company

Plugging Contractor's License No. 12

Address Great Bend, Kansas

(Describe Briefly the manner in which the well was plugged)

196' of 8-5/8" surface casing circulated with cement.

Plugged back with crushed rock to 3475 feet; dumped 4 sax

cement with dump bailer. Top of cement, 3450'. Filled hole with mud

to 190 feet; set rock bridge, dumped 15 sax cement. Top of cement

140 feet. Filled with mud to 35'; set rock bridge and dumped 10

sax cement for cap. Job completed 7/25/56 at 6:30 P.M.

pulled 1200' 5 1/2"

Edwin Petty
District Conservation Agent

RECEIVED
STATE CORP
AUG 2 1956

Date July 25, 1956

PLUGGING
FILE SEC 6 T 2 R 18W
BOOK PAGE 76 LINE 32