

KANSAS

Form CP-3  
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-137-20006-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 31 1967  
10-31-67  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name National Associated Petroleum Company.

Complete Address Petroleum Building, Tulsa, Oklahoma.

Lease Name Neil W. Reeves Well No. 1

Location CNE-NW Sec. 5 Twp. 2 Rge. (E) (W) 21

County Norton Total Depth 3759

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Thoroughbred Drilling Company.

Address        License No.       

Operation Completed: Hour 7:30PM Day 20 Month 10 Year 1967

The above well was plugged as follows:

249'--8 5/8" Surface pipe, cement circulated with 140 Sx.  
Dakota section from 1050' to 1250'.

Circulated hole with heavy mud, pulled DP to 1300' and displaced 100 Sx. cement thru  
DP. Pulled DP to 250' and displaced 25 Sx. cement thru DP. Pulled DP, set bridge @  
40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INDEXED

Signed: N. L. Nichel  
Well Plugging Supervisor

DATE 10/31/67  
INV. NO. 6591-W