

DISTRICT CONSERVATION AGENT'S REPORT

15-147-00659-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION CW $\frac{1}{2}$ NW SW

SEC. 24 TWP. 2 RGE. 19^w

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Weinman 607 Union Hatch

Operator Lewis Dng Co Address Wichita, Kans

Field _____ County Phillips

Total Depth 3533 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 185' circulated with cement - 5 1/2" at 3533' with
250 sax cement behind. Perf at 3312', plugs and chat to
3310' sand to 3300', set 4 sax cement with dump bailer,
pulled 1600', 5 1/2", filled hole with mud to 185', set rock
bridge and 15 sax cement, filled with mud to 40', set rock
bridge and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 24T-2 P. 19W
BOOK PAGE 138 LINE 27

District Conservation Agent

Date 1-14-52

1-18-52