

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

L

200 Colorado Derby Bldg.
Wichita, KS 67202

API Number 15-137-20,217-00-00

Operator's Full Name X O Exploration, Inc.

Complete Address 1776 Lincoln St, #401, Denver, Colorado

Lease Name Whitney Well No. 1

Location SW SW Sec. 21 Twp. 2 Rge. 22 (~~East~~) (West)

County Norton Total Depth 3695'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. and Sun Oil Well Cementing, Inc

Address 801 Union Center, Wichita, Ks License No. _____

Operation Completed: Hour: 9:00 AM Day: 20 Month: August Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows: 8 3/8" - 223-165 sacks Elev. 2238 KB Anh 1819-1850

Hole circulated and filled with mud. 50 sacks cement pumped through drill pipe at 1490'. 50 sacks cement pumped through drill pipe at 300'. Hole filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole cemented with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 21 1981
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9-29-81

INV. NO. 7746-W

Signed [Signature] 8-21-81
Conservation Division Agent