

KANSAS

W
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-137-20083-00-00

RECEIVED
STATE CORPORATION COMMISSION

OCT 11 1972

CONSERVATION DIVISION
Wichita, Kansas

10-11-72

Operator's Full Name Donald L. Snyder,

Complete Address 2701 NW 39th, Oklahoma City, Oklahoma.

Lease Name Green Well No. 1-25

Location NE-NW-SW Sec. 25 Twp. 2 Rge. (E) (W) 23

County Norton Total Depth 3698'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza, Wichita, Kansas. License No.

Operation Completed: Hour 11:30 PM Day 7 Month 10 Year 1972

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 850'.

Circulated hole with heavy mud. Pulled DP to 1075' and displaced 110 Cu. Ft. cement
thru DP from 1075' to 750'. Pulled DP to 220' and displaced 30 Cu. Ft. cement thru
DP from 220' to 115'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Pichak*
Well Plugging Supervisor

INVOICED

DATE 10/11/72

INV. NO. 6453-W