

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 31 1966

10-31-66  
CONSERVATION DIVISION  
Wichita, Kansas

15-137-30069-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Glen N. Rupe et al.

Complete Address: 222 Brown Building, Wichita, Kansas.

Lease Name Young Well No. 1

Location SE-NW Sec. 33 Twp. 2 Rge. (E) (W) 23

County Norton Total Depth 3633

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: March Drilling Company, Incorporated,

Address: 3248 North Halstead, Hutchinson, Kansas. License No.     

Operation Completed: Hour 3:30PM Day 27 Month 10 Year 1966

The Above well was plugged as follows:

182'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulated hole with heavy mud, set plug @ 550' and displaced 20 Sx.

cement thru DP. Heavy mud to 180', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: R. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 10/31/66  
INV. NO. 4199-W