

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15454-00-00
Spot: N2SESW Sec/Twnshp/Rge: 5-18S-12W
990 feet from S Section Line, 3300 feet from E Section Line
Lease Name: EVELEIGH B Well #: 3
County: BARTON Total Vertical Depth: 3350 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN, LLC
Address: 3200 FIRST PLACE TOWER
TULSA, OK 74103

PROD Size: 5.5 feet: 3346 w/115 sxs cmt
SURF Size: 8.625 feet: 215 w/150 sxs cmt

8/108

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/10/2004 11:00 AM
Plug Co. License No.: 32983 Plug Co. Name: STEVE'S WELL SERVICE, INC.
Proposal Rcvd. from: JOHN 'ART' ROLO Company: NADEL AND GUSSMAN, LLC Phone: (913) 434-2916

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 700# hulls - 20 sxs gel.
Log Tech RIH and perfed at 1300' and 725'.
Open hole.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/10/2004 3:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Sanded off bottom to 3315' and dumped 5 sxs cement with a dump bailer.
RIH with tubing to 3240' - pumped 15 sxs gel, followed with 35 sxs 60/40 pozmix
with 200# hulls mixed in - displaced cement.
Pulled tubing to 1320' - pumped 175 sxs 60/40 pozmix with 500# hulls
mixed in to circulate cement out of 5 1/2" casing and 8 5/8" casing.
Shut in 8 5/8" casing and pumped 20 sxs cement. Max. P.S.I. 300#
Relieved pressure and pulled tubing.
Tied onto 5 1/2" casing with a swedge and pumped 20 sxs 60/40 pozmix.
Max. P.S.I. 150#. S.I.P. 100#..

RECEIVED
JUN 16 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #17945

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)



INVOICED

DATE 6-16-04
NO. 2004066682

JUN 14 2004

NADEL & GUSSMAN #3 EVELIGH 'B' N2 SE SW 5-18-12W S3

Contr. JONES DRIG BARTON County

E1810 RB Comm. 5-17-61 Comp. 6-9-61 IP 242 BOPD/ARB

Tops	Depth	Datum	Casing
HEEB	2984	-1174	8" 215 5" 3346
BR LM	3084	-1274	
LANS	3100	-1290	
ARB	3345	-1535	
TD	3350	-1540	

DST 3117-67/30", 5' M, BHP 35#
 DST 3345-50/90", 180' G, 105'
 CL 0, BHP 1050-980#
 CO TD: SWB 1 BOPH, NATL: ACID
 500: SWB 12 BOPH/5 HRS

REDMING SE POOL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

MAILED