

3 022577

15-001-01822.0000

To:

API NUMBER CONTROL NO.20040014-22

STATE CORPORATION COMMISSION

NW,SW,NW 1/4 Sec/Twp/Rge S.16-T.26S.-R.18E.

Wichita State Office Bldg. - PLUGGING SECTION

3500 feet from south section line

130 S. Market, Room 2078

4798 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# STEVENS NO.22Operator License # 101County ALLENOperator: STATE OF KANSAS Fee FundWell Total Depth 800' feetName & FEE FUND PLUGGINGProduction Pipe: 1 1/2" Size Feet 800'

Address _____

Surface Casing: 10" Size Feet 20'AB oil well X Gas Well _____ SWD Well/ Input Well _____

D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICELic. # 30670Address: 19254 FORD ROAD, CHANUTE, KANSAS 66720Company to plug at: Hour: 8:00A.M. Day: _____ 17 Month: 5 2004Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 1 1/2" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED IN AT T.D. ONLY. THE 1 1/2" CASING WAS PARTED AT APPROXIMATELY 60' AND THE TOP 60' REMOVED. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL FULL OF CEMENT INSIDE AND OUTSIDE THE 1 1/2" CASING.

Plugging Proposal Received by: CLAYTON P. TITELPlugging attended by Agent: All X Part _____TECHNICIAN
None _____Operations Completed: Hour: 1:00P.M. Day: _____ 17 Month: 5 2004Actual Plugging Report: THE STUMP OF 1 1/2" CASING WAS OVERSHOT AND 3/4"PIPE WAS RAN INTO THE 1 1/2" CASING TO 700'. CEMENT WAS PUMPED INTO THE 3/4"PIPE TO CIRCULATE THE 1 1/2" FULL OF CEMENT FROM 700' UP. THE 3/4" PIPE WASREMOVED. 1" PIPE WAS RAN INTO THE 1 1/2" AND 10" ANNULUS TO 625'. CEMENTWAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 10" SURFACECASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROMSURFACE. 268 SACKS WERE PUMPED INTO THIS WELL.Remarks: (GPS SESSION PT. NO.22)(THIS WELL WAS UNNUMBERED ON THE LEASE MAP)(If additional description is necessary, use BACK of this form.)I DID observe this plugging.

Signed:


TECHNICIAN

RECEIVED

JUN 01 2004

KCC WICHITA

