

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21247-00-00
Spot: S2N2 Sec/Twnshp/Rge: 12-32S-19W
2164 feet from N Section Line, 2529 feet from E Section Line
Lease Name: CAVALRY Well #: 1-12
County: COMANCHE Total Vertical Depth: 5800 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

CIBP Size: feet: 5600 WITH 2 SX CMT
PROD Size: 5.5 feet: 5796 WITH 150 SX CMT
SURF Size: 8.625 feet: 611 WITH 325 SX CMT **\$188⁵⁰**

Well Type: GAS UIC Docket No: Date/Time to Plug: 05/28/2004 9:00 AM

Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION

Proposal Rcvd. from: JOHN SWINFORD Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 5600' WITH 2 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 05/28/2004 9:45 AM

Witness Type: COMPLETE (100%)
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 5724'. CIBP @ 5600' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN 5 1/2" CASING & RUN IN 2 7/8" TUBING TO SPOT PLUGS THROUGH. 1ST PLUG AT 630' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5656	5660		

RECEIVED
JUN 16 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2900' OF 5 1/2" CASING.

Plugged through: TBG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 6-16-04
SER. NO. 2004061679

Form CP 323