

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-01037-00-01
Spot: NENESE Sec/Twnshp/Rge: 32-30S-12W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: OLSON OWWO Well #: 1
County: BARBER Total Vertical Depth: 4000 feet

Operator License No.: 30128
Op Name: WHITE, KENNETH S.
Address: 2400 N. WOODLAWN, SUITE 115
WICHITA, KS 67220

PROD Size: 4.5 feet: 3983 WITH 150 SX CMT
SURF Size: 8.625 feet: 207 WITH 170 SX CMT

\$130⁰⁰

Well Type: SWD UIC Docket No: D27600.0 Date/Time to Plug: 06/01/2004 10:45 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: PER KCC RULES AND REGULATIONS. FILL HOLE W/SAND TO 3700' AND DUMP 50 SX CMT, SHOOT CASING FOR RECOVERY, PULL CASING & PLUG @ 730' W/10 SX GEL AND 50 SX CMT, 50 SX CMT @ 230' & 20 SX CMT @ 40' TO SURFACE 60/40 POX, 6% GEL.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/01/2004 11:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:
PBTD 3962'. 4 1/2" PACKER PULLED UP TO 3200' & LOST. LEFT PACKER IN HOLE. PUMPED DOWN 4 1/2" CASING WITH 50 SX CMT. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 730' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 240' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3940	3950		
3736	3828		

RECEIVED
JUN 16 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2960' OF 4 1/2" CASING.
Plugged through: CSG

District: 01
RECEIVED
JUN - 7 2004
KCC Dodge City

Signed Stephen J. Pfeifer
(TECHNICIAN)
INVOICED
DATE 6-16-04
INV. NO. 2004061683

Form CS-278