

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22428-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 7-31S-2W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: MEYER Well #: 1-7
County: SUMNER Total Vertical Depth: 3363 feet

Operator License No.: 30129
Op Name: EAGLE CREEK CORPORATION
Address: 150 N. MAIN, STE 905
WICHITA, KS 67202

SURF Size: 8.625 feet: 324

30
\$109

Well Type: DH UIC Docket No: Date/Time to Plug: 05/20/2004 3:00 AM
Plug Co. License No.: 5892 Plug Co. Name: BERENTZ DRILLING CO., INC.
Proposal Rcvd. from: JIMMY HERALD Company: BERENTZ DRILLING CO., INC. Phone: (316) 685-5908

Proposed Plugging Method: 35 sxs @ 600'; 35 sxs @ 375'; 25 sxs @ 60'; 10 sxs in rathole.
35 sxs @ top of Arbuckle if penetrated.

RECEIVED
KCC DISTRICT #2
JUN - 7 2004
WICHITA, KS

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE
Date/Time Plugging Completed: 05/20/2004 5:45 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Did not drill to Arbuckle.

Pumped 35 sacks of cement at 600'. Pulled drill pipe to 375' and pumped 35 sacks of cement.
Pumped 25 sacks of cement at 60' to surface.

10 sacks of cement in rathole.

60/40 posmix with 4% gel.

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 15 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: ACID SERVICES #8485

Plugged through: DP

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 6-15-04
INV. NO. 2004061634