

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-01991-00-00  
Spot: SENENW Sec/Twnshp/Rge: 27-18S-10W  
990 feet from N Section Line, 2970 feet from E Section Line  
Lease Name: HABIGER Well #: 3  
County: RICE Total Vertical Depth: 2700 feet

Operator License No.: 4707  
Op Name: BOXBERGER, CARL OIL, INC.  
Address: PO BOX 1604 3111 - 10TH STREET STE  
GREAT BEND, KS 67530

PROD Size: 7 feet: 2700 75 SX CMT  
SURF Size: 10 feet: 227 CIRCULATE

*\$5775*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/28/2004 3:30 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: Sand off perms to 2600' & put 7 sxs cement on top; perf at 1225', 875' & 280'; run tubing to 1225' & pump 50 sxs; pull tubing to 875' & pump 50 sxs; pull tubing to 280' & circ to surface.

RECEIVED  
KCC DISTRICT #2  
JUN - 7 2004

WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER

Witness Type: PARTIAL

Date/Time Plugging Completed: 05/28/2004 4:45 PM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Set CIBP at 2600' and put 2 sacks of cement on top. Perforated at 1225', 875', and 280'. Ran tubing to 1225' and pumped 50 sacks of cement. Pulled tubing to 875' and pumped 50 sacks of cement. Pulled tubing to 280' and circulated cement to surface.

Top	Bot	Thru	Comments
2657	2663		

Topped off on 6/1/2004 with 45 sacks of cement -- Allied ticket #18110.

60/40 posmix with 4% gel.

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 15 2004

Remarks: ALLIED CEMENT #18108

Plugged through: TBG

District: 02

Signed

*Virgil Clothier*  
(TECHNICIAN)

INVOICED

DATE 6-15-04  
INV. NO. 2004061673