

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20685-00-00
Spot: SENW Sec/Twnshp/Rge: 36-34S-35W
1980 feet from N Section Line, 1980 feet from W Section Line
Lease Name: KINNEY CHESTER SAND UNI Well #: 804
County: STEVENS Total Vertical Depth: 6632 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ
HOUSTON, TX 77227

COND Size: 20 feet: 20 WITH 2 YDS CMT
PROD Size: 5.5 feet: 6631 WITH 175 SX CMT
SURF Size: 8.625 feet: 1638 WITH 1200 SX CMT

#215 54

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/20/2004 12:00 PM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 25 SX CMT & 300# HULLS. PLUG AT 1650' WITH 50 SX CMT. PLUG AT 600' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE

Witness Type: NONE

Date/Time Plugging Completed: 05/24/2004 2:00 PM

KCC Agent: KEVIN STRUBE

Actual Plugging Report:

Perfs:

PBTD 6588'. PUMP 25 SX CMT & 300# HULLS FOR BOTTOM PLUG. 1ST PLUG AT 1650' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 30 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.


Top	Bot	Thru	Comments
6522	6533		

RECEIVED
JUN 14 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2401' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed _____

Kevin Strube

(TECHNICIAN)

INVOICED

DATE 6-15-04

INV. NO. 200406071

Form CP-23

[Signature]