

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-20652-00-00  
Spot: NENW Sec/Twnshp/Rge: 36-34S-35W  
660 feet from N Section Line, 1980 feet from W Section Line  
Lease Name: KINNEY CHESTER SAND UNI Well #: 802  
County: STEVENS Total Vertical Depth: 6750 feet

Operator License No.: 5447  
Op Name: OXY USA, INC.  
Address: PO BOX 27570 5 E GREENWAY PLZ  
HOUSTON, TX 77227

CIBP Size: feet: 5900 WITH 2 SX CMT  
COND Size: 20 feet: 20 WITH 2 YDS CMT  
PROD Size: 5.5 feet: 6749 WITH 175 SX CMT  
SURF Size: 8.625 feet: 1663 WITH 800 SX CMT

4219<sup>38</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/27/2004 3:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: SEST CIBP @ 5860' WITH 2 SX CMT. PLUG AT 1700' WITH 70 SX CMT. PLUG AT 600' WITH 30 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: NONE  
Date/Time Plugging Completed: 05/28/2004 5:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 6698'. SET CIBP @ 5900' WITH 2 SX CMT. 1ST PLUG AT 1700' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 30 SX CMT. 3RD PLUG AT 40-0' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6539	6543		
6515	6553		
6497	6505		

RECEIVED  
JUN 14 2004  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2340' OF 5 1/2" CASING.  
Plugged through: CSG

District: 01

RECEIVED  
JUN - 3 2004  
KCC Dodge City

Signed

*Kevin D. Strube*  
(TECHNICIAN)  
INVOICED  
DATE 6-15-04  
VV. NO. 2004061671

Form *[Signature]*